Encircle PM / Lead Sheet: Setup and Oversight

Unofficial. Current Encircle Hydro, from the help center (checked Oct 18, 2026). MC = moisture content. [verify] = check in app.

Techs

- *Techs use the Tech sheet for daily work. This sheet is setup and oversight.*

Hydro Job Setup

- **Open:** **Claim** > **Hydro** > **Tasks** > **Start Here**
- **Loss:** **Source of Loss and Category of Water** > category > **Complete**
- **Chamber:** **Drying Chamber** > rooms, **Affected/Unaffected** > **Done** > name > **Complete Task**
- **Chamber first, then psychrometrics. It unlocks the chamber tasks.**
- **Air:** **Exterior Reading**, **Unaffected Area Reading** (no chamber needed); **Affected Area Reading** per chamber; **Dehumidifier Readings** each dehu

Materials and dry standards

- **Dry standard:** **Dry Standard** > material > Meter **Change** > **Change Meter** > **Add Meter Photo** > check MC > **Drying Variance** (10%) > **Save**
- **Not listed:** **+ Add** on the material list
- **Next material:** red **+** on the Dry Standard list
- *One per wet material, read in a dry area. Hydro remembers the meter.*

Moisture points (no map)

- **First:** **Moisture Points** > **Place moisture points** (by room) > material > **Done**
- **More:** tap the room > red **+** > **Moisture Point** > material > **Done**
- **One point per affected material, per room**
- *Map only if a carrier/job asks:* ***Room Moisture Map*** *>* ***Place*** *>* ***Place Existing*** *>* ***Place All***

Equipment count and settings

- **Count:** **Room & Affected Area Dimensions**, then **Equipment Calculation** > **Calculate**
- **Settings:** **Drying Chamber Settings** > **Stabilization/Drying/Dry Confirmed** > **Save**
- **Later:** **Hydro** > chamber > **⋯** > **Manage Drying Chamber**
- **Past visit:** **Tasks** > **⋯** > **Change Visit**

Floor Plan

- **Scan:** **Claim** > **Add Floor Plans** > **Let's Scan** > red **record**
- **Access:** Standard/Admin users (not Limited)
- **Sketch:** plan > **Create Sketch** > name > **Save** > crop > **Save** > room > **Save**
- **Fix size:** plan > **wrench** > describe > **Send**

Forms and signatures

- **On site:** **Documents** > **Generate Report** > **PDF Report** > form
- **Remote:** **Share** > **Add Link** > email/SMS > docs > **Preview & Sign** > **Share**

Reports

- **Moisture:** **Documents** > **Generate Report** > **PDF Report** > **Hydro Full/Summary/Equipment/Carrier Report** [verify on mobile]
- **Job:** **Encircle PDF Report** > **Everything** > **Show Psychrometrics & Drying Information**: **Yes** > **Save**

Xactimate import

- **Import:** **Data Request** > **Interior Walls** > Floor Plan ID as **Claim Number** > **Submit** > Sketch > **Data Import** > **Import**
- *Integration must be on. $10 per import; ceiling comes in at 8 ft.*